

---

# Overview of the ITER Heating and Current Drive Systems

**Paul R Thomas**  
**for the**  
**ITER Organization and the Domestic Agencies**

ITER Organisation  
Route de Vinon sur Verdon, 13115 St Paul Lez Durance, France

*The views and opinions expressed herein do not necessarily reflect those of the ITER Organization.*

# Baseline Heating and Current Drive Systems

---

## *73 MW to achieve H mode and $Q=10$*

- 2 Heating (HNB) Neutral Beams at 1 MV (2X16.5 MW) and Diagnostic (DNB) Neutral Beam at 100 kV
- Electron Cyclotron System (EC) (20 MW at 170 GHz)
- Ion Cyclotron System (IC) (20 MW at 40-55 MHz)

## *Upgrade for a later phase of Steady-State Operation*



- Lower Hybrid Current Drive (LH) (20-40MW at 5GHz)
- Potential power increases for EC, IC and NB

- K.Ikeda et al., “Progress in the ITER Physics Basis”, Nuclear Fusion **47** (2007).
- F.Wagner et al., Plasma Phys. Control. Fusion **52** (2010) 124044.



# Neutral Beam Systems

- 2 (+1) HNB: Heating Neutral Beam
- 1 DNB: Diagnostic Neutral Beam




- 2 N-NBIs (+1)
- $P_{\text{beam}} = 16.5 \text{ MW}$
- $I = 40 \text{ A}$
- $V = 1 \text{ MV}$
- $T_{\text{pulse}} = 3600 \text{ s}$

- Requirements substantial advance on existing NBI so a Neutral Beam Test Facility is being prepared by Consorzio-RFX at Padua in Italy.

- R Hemsworth et al., Nucl. Fusion **49** (2009) 045006


# Neutral Beam Injector

- The beamline components are identified below.
- Other important components include the cryo-pump, vessels fast shutter, duct, magnetic shielding, and residual magnetic field compensating coils.



# Technical Challenges associated with ITER NB (i)

## Large scale negative ion source



### Challenges:

- High current density 200A/m<sup>2</sup> in D<sup>-</sup> / 300A/m<sup>2</sup> in H<sup>-</sup>
- High reliability / low maintenance frequency , 2years
- Stable long pulse operation (for 1hour ITER pulse)
- Spatial and temporal uniformity ± 10%


## 5 stage Multi Aperture Multi Grid accelerator

- 200kV per stage
- 1280 apertures in 4 x 4 matrix


## High heat-flux components, like calorimeter or Residual Ion Dump

- Hypervapotron or Swirl-tube technology
- Actively cooled
- CuCrZr

RID: Remove remaining charged ions in the beam after neutralisation




High Heat Flux Panels



Calorimeter:  
Used to measure beam power and profile

# Technical Challenges associated with ITER NB (ii)

## 1MV HV Bushing for the Heating Neutral Beam Injector




High voltage, cooling water and H<sub>2</sub>/D<sub>2</sub> gas are fed to the beam source through HV transmission line (SF<sub>6</sub> gas insulation):

Issues:

- HV Holding (1MV)
- Tritium confinement
- Vacuum leak tightness


- Largest ceramic ring with brazed Kovar plate in the world produced for HV Bushing




## Development of an all-metal seal isolation valve of ~ 1.6m diameter

Used to isolate the injectors from the ITER vacuum vessel for interventions:


- Weight more than 14.5 tons
- Maximum permissible leak rate  $1 \times 10^{-10}$  Pa m<sup>3</sup> /s
- Has to withstand 20MPa in injector, vacuum in ITER vacuum vessel



# Duct Liner Remote Handling



DLM Top/bottom Panel Transporter




CuCrZr deep drilled panels  
Top/bottom & sides

Neutron shield  
316LN



# 170 GHz ITER EC System




- Provide auxiliary heating (20MW) to assist in accessing H mode and achieve  $Q=10$ .
- Provide steady state on-axis and off-axis current drive in the range of  $0 < \rho_T < 0.5$ .
- Control MHD instabilities by localized current drive.
- Assist initial breakdown and heat during current ramp-up.



# EC Launchers

Challenges include:



- Transmit up to 20MW CW using rotating mirror systems
- Provide nuclear shielding and confinement
- Maintenance of in-vessel via remote handling operations



# Steering Mirror

EU developing novel frictionless back-lash free steering mirror



- Survive in ITER's nuclear environment
- Withstand up to  $5\text{MW/m}^2$  on mirror surface
- Steer beams over  $\geq 24^\circ$
- Reliably position beams with steering accuracy  $\sim 0.025^\circ$



# Diamond Window

Diamond window provides:

- $\geq 1.1\text{mm}$  thick disk  $\sim 76\text{mm}$  in diameter
- Compatible with transmission of 2.0MW
- Provides confinement of tritium in ex-vessel waveguide
- Configuration allows in-situ leak testing and isolation with all-metal gate valve





Two Diamond window housing designs (JAEA and F4E/KIT) being tested:

- Both using JAEA 170GHz 1MW CW test facility
- Achieved  $\geq 0.5\text{MW}$  for  $\geq 20\text{s}$  (limited by PS problems)
- Continued testing planned for November 2011
- Aim for  $\geq 1\text{MW}$  and long pulse operation
- Concern for long term reliability of window (present experience is  $\leq 4000\text{sec}$  integrated on-time)

# Remote Handling

Critical component required to use RH for maintenance:

- Removal and re-insertion of launcher in Port
- Replacement of blanket shield module (in hot cell)
- Replacement of steering mirror assembly (in hot cell)
- Replacement of internal shielding blocks (in hot cell)







The image cannot be displayed. Your computer may not have enough memory to open the image, or the image may have been corrupted. Restart your computer.


# Ion Cyclotron H & CD System

- Two antennae (equatorial port plugs) (EU)
- Transmission and matching systems (US)
- RF sources (8x3MW + 1 spare, 40-55MHz, for 20MW in plasma) (IN)
- High Voltage power supplies (IN)



- Dimensions: 2.1 m H x 1.7 m W x 3.6 m L
- All components actively cooled
- Max. dry mass: 45 metric tons
- 4 x 6 radiating straps grouped in 8 poloidal triplets

# IC Antenna: Key design developments(i)



# IC Antenna: Key design developments(ii)

## Bulkhead Layout


Extensive work laying out revised cooling water system, diagnostic feedthroughs, vacuum lines etc

## RVTL

Dimension Changes in sympathy with RF design, development programmes underway, support on Window R&D

## Shimming

Rear Hydraulic components optimised for layout, simplified 2 pipe supply shaft, reflectometry incorporated



## Rear Shield Cartridge

Extended, with now deep drilled cooling solution developed to attenuate neutron streaming

# IC Source Specifications

Specification	Level & Units
Nominal output power	2.5 MW CW/ 3 MW CW
Pulse duration	2000 s/3600s
Duty cycle	1/4
Maximum average VSWR	2/1.5
Transient VSWR at any phase	2.5 /2 (1 s max. & 10% duty cycle)
Accuracy of output power	5% max
Frequency Range	35-65 MHz / 40-55 MHz
Power mod. range at the load	2kW-3 MW
Max amplitude mod. frequency	100Hz
Max. Output harmonic level	-20 dBc
Max phase mod. frequency	10kHz
Overall end stage electrical efficiency (%)	≥65 (matched) ≥45 (worst unmatched)
O/P impedance	50Ω

Specifications

## Output power - qualification

programme has been launched in INDA:


- Representative test of one chain up to final stage.
- ITER India is developing source chain up to predriver; an industrial partner develops the driver and endstage

## Plan for the **combiner**:

- Definition of the design specifications and margins
- Definition of RF amplitude and Anode voltage regulations
- specific test plan - *this is not an unusual circuit configuration*

# Future upgrade - LHCD

Klystron	Design Target	Achieved Performance of Prototypes	Comments
5 GHz (Toshiba)	500kW/ CW VSWR 1.4	303 kW / CW (VSWR=1) 508 kW / 0.5s (VSWR=1)	Development For KSTAR
4.6 GHz (CPI)	250 KW/ CW	Used in Alcator <u>C-Mod</u>	On going production for EAST
3.7 GHz (TED)	700kW / CW	767kW/CW (VSWR=1) 670kW/CW (VSWR=1.4)	Installed and used in Tore Supra



(a) Prototype of 5 GHz tube and (b) prototype of 3.7 GHz;  
(c) 4.6 GHz tubes in operation on Alcator C-Mod.

- Progressed on voluntary basis by interested Parties
- Layout and interfaces ensured by IO

REF: G.T. Hoang, et al., A lower hybrid current drive system for ITER, Nucl. Fusion **49** (2009), p. 075001.

# Procurement Status

	Reference	Signature Date	klUA Value
16	5.3.P7A.IN.01 Diagnostic neutral Beam Power Supply	19 April 2009	9.70000
24	5.3.P6.EU.01 Power Supply for Heating Neutral Beam ( Low Voltage)	13 July 2009	31.38200
31	5.1.P3.IN.01.0 IC H&CD RF Power Sources	5 February 2010	18.00000
35	5.3.P7B.IN.01 Diagnostic Neutral Beam Line	22 March 2010	13.10000
37	5.1.P2.US.01 IC Transmission Lines	30 April 2010	7.35400
41	5.2.P2.US.01 Electron Cyclotron Main Transmission Lines	12 May 2010	12.71700
46	5.3.P9.EU.01.0 Neutral Beam Test Facility Components	27 October 2010	27.00
47	5.3.P9.IN.01 Neutral Beam Test Facility Components (Spider and Calorimeter)	15 December 2010	0.91
3	5.1.P4.IN.01 IC H&CD Radio Frequency Power Supply	March 2011	6.9
30	5.2.P3.RF EC Gyrotrons	(sept 2011)	9.86
35	5.2.P3.IN.01 EC RF Gyrotrons	(oct 2011)	2.69
36	5.2.P3.EU.01 EC RF Gyrotrons	(oct 2011)	9.86
		<b>Total</b>	<b>149.5</b>

- Most H&CD functional specification PAs have been signed.
- Build-to-Print designs are in PDR or FDR phases.

*Note: 1klUA ~ 1.55M€*

---

# Thank you for your attention!

## Associated presentations at this conference:

D. Rathi, DEVELOPMENT & INTEGRATION OF THE ICH & CD SYSTEM CONFIGURATION IN THE ITER TOKAMAK COMPLEX AND AUXILIARY BUILDINGS **(SP3-20)**

H.DECAMPS, THE -1 MV DC ITER NEUTRAL BEAM POWER SUPPLY **(SP3-48)**

T.GASSMANN, PROGRESS IN CONCEPTUAL DESIGN OF THE HIGH VOLTAGE POWER SUPPLIES FOR ITER EC SYSTEMS **(SP3-44)**



D.CAMPBELL, CHALLENGES IN OPERATION AND CONTROL OF ITER **(SO1B-1)**

R.Hawryluk, PROGRESS TOWARD ITER **(SPL1-1)**

---


# Spare Slides

# The NBI Duct Liner





**CuCrZr deep drilled panels  
Top/bottom & sides**

**Neutron shield  
316LN**



# Electron Cyclotron H & CD System

5 Parties provide in-kind procurement of the 4 subsystems



Matching Optics Unit

JA Gyrotron test bed

Evacuated Transmission Line



Cryogen free magnet for 1MW gyrotron (Cryomagnetics, Inc.)

- Cryo-magnets and condensers for gyrotrons (EU, JA, RF, IN)

- HV power supplies (60kV, 100A) and (50kV, <1A) (EU, IN)
- Evacuated waveguide components (US, EU, JA)
- Cooling manifold systems (JA, EU, RF, IN, US)
- Control systems (JA, EU, RF, IN, US)

# IC Source Block Diagram

