

Physics programme for initial operation of Wendelstein 7-X


Hans-Stephan Bosch
Max-Planck Institute for Plasma Physics
Greifswald, Germany



H.-S. Bosch

17th Int. Stellarator/Heliotron Workshop, October 12 – 16, 2009, Princeton, NJ


1-YKA-Y000x




- **stepwise approach**
- **1st operation phase with 10s @ 8MW, inertially cooled divertor and only partial cooling of in-vessel components**
- **shut-down (15 months) for completion and hardening**
- **2nd operation phase to approach 30min @ 10MW**

- **Construction, status and schedule**
- **Commisioning**
- **Experimental set-up for first operation phase**
- **Initial physics programme**
- **Summary**

Wendelstein 7-X main components





- Preparation of components is organised independently from the assembly activities
- The module assembly is carried out on different mounting stands in two halls




Coils are threaded across the plasma vessel




Thermal insulation is completed



- The coil support structure is positioned in front of the 7-coil pack
- Coils are bolted to the central support ring




- The flip-symmetric half-modules are aligned
- The step-flange is bolted and the vessel half-modules are welded
- Thermal insulation, Inter-coil structure are completed




Module 5, February 2009



Cryopiping to be welded




Bus-bars to be mounted




Comprehensive collision checks required during design, layout and installation of the two systems



28 electrical joints between bus-bars and coil conductor are welded and insulated





October 12, 2009

- The module assembly is organised in parallel
- 4 out of 5 modules are in the works
- The assembly schedule still contains half a year buffer times
- Assembly will be finished in summer 2014


- Construction, status and schedule
- **Commisioning**
- Experimental set-up for first operation phase
- Initial physics programme
- Summary

Commissioning of W7-X has three steps with increasing levels of system integration.

1. **Local commissioning** of the technical components. This includes instrumentation and local control and will be done before the end of W7-X assembly.
2. **Integrated commissioning:** Stepwise integration of these components into the overall system, the central device control and the central data acquisition system.

This process is centred around four major work packages


- Vacuum operation
 - Cryogenic operation
 - Magnetic field operation
 - First plasma
3. **Transition into plasma operation:** Demonstration that the overall system meets the basic technical requirements and enables scientific use of the device. This includes plasma start-up and control.




- first planning of the four work packages available
- milestones have been identified
- detailed planning has to be worked out (optimization of work steps)

- Construction, status and schedule
- Commissioning
- **Experimental set-up for first operation phase**
- Initial physics programme
- Summary

- inertially cooled „test divertor“ – 10 modules
 - conventional graphite tiles
 - same geometry as HHF-divertor
 - adjustable frame
- ⇒ Allows much more robust operation and check of magnetic geometry, in preparation of HHF-divertor
- operation limited to 5-10s at 8MW power
 - no cryo pumps
 - limited water-cooling inside plasma vessel
 - design review in March 2009
 - manufacturing has started





prototype graphite module



The test divertor will be replaced by the HHF-divertor after the first operation phase.

- 8 x 1 MW ECRH @ 140 GHz available (30min)
 - tuning to 105 GHz at 50% output power possible
 - switch between X and O polarisation
 - 4 ECRH beam launchers with 3 individual front steering mirrors
 - steering range $-15^\circ < \Phi_{\text{tor}} < +35^\circ$ and $-25^\circ < \theta_{\text{pol}} < +25^\circ$ with 25 %
 - cooled reflector tiles on the high field side
-
- two NBI boxes with two beams each
 - 7 MW for H (55 keV) and 10 MW for D (60 keV) operation
 - copies of the AUG system with RF PINIS
 - rather radial injection $\pm 7.44^\circ$
 - about 50% Polish contribution (decision pending)



	concept	design	manufacturing	cooperation
I: plasma core spectroscopy				
diagnostic beam	●	●	◐	FZJ/Budker (Rus)
CXRS	◐	◑	◑	
soft x-ray tomography	●	◐	◑	
pulse height analysis	●	◐	◑	IPPLM (PL)
bolometry	●	◐	◑	
C/O-monitor	●	◐	◑	U-Opole (PL)
HEXOS VUV spectroscopy	●	●	●	FZJ
neutron counters	●	◐	◑	PTB
II: microwaves and laser diagnostics				
thomson scattering	●	◐	◑	IPP-AUG
interferometry	◐	◐	◑	FZJ
electron cyclotron emission	●	●	◐	



	concept	design	manufacturing	cooperation
III: divertor diagnostics and magnetics				
neutral gas gauges	●	●	◐	
divertor thermography	●	◑	◑	
divertor thermo couples (TDU)	◐	◐	◑	
video diagnostics	●	●	◐	KFKI (Hun)
magnetic diagnostics	●	◐	◐	
langmuir probes (TDU)	●	●	◑	
H α diagnostics	●	◑	◑	
visible spectroscopy	◐	◑	◑	
thermal Helium beam	●	●	◑	FZJ
laser-induced fluorescence	●	◐	◐	FZJ

- about 20 different diagnostic systems will be available for the first operation phase
- development structured in three topical groups
- progress presently hampered by bottlenecks in design capacity
- steady state CoDaC system

- Construction, status and schedule
- Commissioning
- Experimental set-up for first operation phase
- **Initial physics programme**
- Summary

- Development of the programme has started with a dedicated seminar series, involving all senior scientists and covering all physics aspects.
- The final goal of the first operation phase is to develop an integrated high-density scenario with configuration control and edge conditions suitable for divertor operation.
- This scenario forms the basis for high-power steady-state operation to be explored during the second operation phase.
- The first operation phase of Wendelstein 7-X can be broken down in a number of (technical) milestones and intermediate scientific aims.


Nr.	milestone/work package	4				2015				2016				2017			
		Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	
1	vacuum conditions achieved			◆ 12.09.													
2	magnet system cold			◆ 07.11.													
3	2.5T magnetic field achieved						◆ 10.04.										
4	magnetic field structure confirmed						◆ 01.05.										
5	diagnostic systems ready						◆ 01.05.										
6	heating systems ready						◆ 01.05.										
7	first plasma						◆ 15.05.										
8	long pulse plasma						◆ 29.05.										
9	symmetry verification						◆ 26.06.										
10	density control investigations																
11	X2-heating up to cutoff																
12	confinement properties																
13	impurity control investigations																
14	tolerable divertor load scarios																
15	X2-current drive for edge iota tuning																
16	dense NBI driven plasmas																
17	divertor high-recycling regime																
18	O2-heating and cutoff																
19	shut down for completion															◆ 15.05.	



**combined ray tracing and
1D transport calculations**

5 ECRH-beams

$P_{\text{ECRH}} = 5 \text{ MW}$




standard configuration

$B_{\text{max}}(0) = 2.56 \text{ T (vac)}$

$\langle \beta \rangle = 2\%$

- **plasma startup 0.7MW X2 at 140 or 104 GHz**
- **low density plasma $\leq 1.2 \cdot 10^{19} \text{ m}^{-3}$**
- **high electron temperature $> 4 \text{ keV}$**

magnetic flexibility of the device





- variation of the toroidal mirror component varies $\epsilon_{\text{eff}} \sim 0.0 \dots 0.1$ varies χ_e
- verification of reduced $1/\nu$ transport in the X2 4MW discharge scenario
- confinement scaling and comparison to ISS04
- configurational effect on $\langle j_{\parallel} \rangle / \langle j_{\perp} \rangle$ (Shafranov shift, τ -profile)
- MHD stability limits? $\leftarrow \langle \beta \rangle$ too low
- fast particle confinement? $\leftarrow \langle \beta \rangle$ too low



Predictive transport simulations for a variation of the mirror ratio

$$n_e = 10^{20} \text{ m}^{-3}$$

6 MW ECR heating



sc: Standard Configuration **W=3.5 MJ**
hm: High Mirror conf. **W=2.6 MJ**



Temperatures and plasma energy are higher for standard configuration.

However, bootstrap current increases edge ι and must be compensated in this case.

Stellarators have a soft density limit with the scaling $n_{DL} = 1.46 (P/V)^{0.48} B^{0.54}$ ← verify


impurity accumulation at higher densities

the aim is stationary plasma with $P_{rad} < 50\% P_{heat}$

- reduction of impurity confinement
 - drag forces at the plasma edge?
 - role and control of ELMs?
 - role of turbulence?

Note:

temperature screening does not occur in stellarators, even for positive radial electric field (e-root)



experience with W7-AS


- experience with W7-AS island divertor
- good modelling capabilities with EMC3/EIRENE
- divertor target overload at $\iota=1$ by factor ~ 2 due to
 - coil alignment \rightarrow field errors $B_{11}/B_0=1-5 \cdot 10^{-4}$
 - divertor misalignment 1-2cm
 - additional impact of $E \times B$ drift

To be investigated:

1. flux surface structure (islands if possible)
2. strike line locations
3. strike line extensions (length & width)
4. power load distribution within strike lines


Resulting actions:

divertor re-alignment, sweep coils B_{33} , trim coils B_{11}




power load on target

EMC3/EIRENE



thermography



- Fabrication of components well under way/finished
- Assembly on 4 out of 5 modules in progress
- Commissioning will start in summer 2014

- Test divertor unit to study operation limits and develop divertor scenarios
- 8MW ECRH and 7 MW NBI
- Diagnostics sufficient to conduct the initial program is being prepared

- Scientific program has been developed by the W7-X team – first steps:
 1. Low density ECRH heating scenarios
 2. Confinement studies at moderate β
 3. Density limits and impurity transport
 4. Tolerable divertor loads



Thank you !

Commissioning of W7-X has three steps with increasing levels of system integration.

1. Local commissioning of the technical components. This includes instrumentation and local control and can mostly be done before the end of W7-X assembly.
 - device control, safety control, data acquisition
 - vacuum systems
 - water cooling/baking system
 - wall conditioning systems (glow discharge, HF-conditioning)
 - cryo plant and He distribution system
 - coil power supplies including QD system
 - gas injection system
 - start-up diagnostics
 - Heating systems (ECRH, NBI)
2. Stepwise integration of these components into the overall system, the central device control and the central data acquisition system.
3. Demonstration that the overall system meets the basic technical requirements of the W7-X system specification and enables scientific use of the device. This includes plasma start-up and control.


- 1. Vacuum (Vacuum systems, control, instrumentation, conditioning systems)**
 - leak tightness of plasma vessel and outer vessel, evacuation
 - leak tightness of water and He cooling pipes, cooling water flow adjustments
 - cleaning of vacuum vessel, wall conditioning, baking
- 2. Cooling (cryo plant, instrumentation, control system)**
 - leak tightness of *cold* cooling pipes
 - cryogenic He-flow adjustments
 - cool down of magnet system
 - » insulation (heat balance, heat leaks)
 - » movements during cool-down (check for collisions)
- 3. Magnetic field (power supplies, QD-system, control system, flux surface measurement)**
 - initial operation of magnet system and magnet safety system
 - superconductivity (especially in joints)
 - forces and movements under load
 - » monitoring by strain gauges, distance sensors and contact sensors
 - » Comparison with predictions from finite element codes
 - magnetic surfaces (at low field and at higher field)

fluorescent method:
interaction of e-beam with fluorescent detector
in a fixed plane → 2D Poincaré plot



- rod with ~ 2mm diameter
- highly transparent ~ few 10 transits
- small details visible (e.g. magn. axis, island)
- duration: ~10s/flux surface (manipulator)
~0.5h/magnetic configuration

field line tracing in background gas:
excitation in background gas by e-beam
→ 3D trace in torus



W7-AS: 35 transits \approx 450m
W7-X: 10-15 transits expected

- magnetic axis, X-points, separatrix
- possible calibration source
for diagnostics

Start of operation

- **basic divertor operation and density control**
- **approach X2-density limit**
- **prove good confinement/neoclassical optimisation/MHD-stability**
- **achieve impurity transport control**
- **tolerable divertor load at full heating power**
- **X2 off-axis current drive for bootstrap current compensation**
- **approach O2-density limit**
- **divertor high-recycling regime**
- **first O2 off-axis current drive experiments**

Shut down (15 months): replacement of divertor modules and hardening

- **operation of actively cooled divertor**
- **step-wise approach towards 10MW 30min shots**
- **long-pulse discharge scenario optimisation**

Bundle of measures to stabilise the completion date mid 2014 (BMBF workshop Sept 2007)

- Reduction of complexity
- Reduction of project risks
- Acceleration measures (by 2 years)

	acceleration	assembly risks	delivery risks	budget risks	operation risks
assembly based on 96h/week = 2 shifts on 6 days/week	×				
additional assembly equipment for parallel works	×				
parallelisation of port assembly	×				
shift of work packages into component preparation	×				
omission of 45 ports			×		×
introduction of 68 weeks buffer time on the critical path			×		
only partial installation of cooling circuits			×		×
start with 8MW ECRH and 10MW NBI					×
Start with inertial test divertor – staged approach to steady-state			×	×	×

Cf. Annex 1-B and Report Bosch