

SOFE, June, 2011



Key Features in the Operation of the KSTAR

Jong-Gu Kwak and the KSTAR Team

*KSTAR Research Center
National Fusion Research Institute*

Brief history of the past 4 years

- **1st campaign (2008)**

- 2007. 9 Device construction
- 2008. 4 SC magnet cool-down (4.5 K)
- 2008. 5 TF operation up to 15 kA (1.5 T)
- 2008. 6 ~ 7 First plasma up to 107 kA (ECH preionization)

- **2nd campaign (2009)**

- 2009. 10 Plasma current up to 320 kA (ECH 110 GHz, 2 T)
- 2009. 11 TF magnet operation up to 35 kA (3.5 T @ R=1.8 m)

- **3rd campaign (2010)**

- 2010. 7 Baking of PFC & vacuum vessel
- 2010. 9 ~ 10 IVC coil operation, NBI beam injection
- 2010. 10 ~11 Plasma startup, shaping, and H-mode

- **4th campaign (2011)**

- 2011. 5 Baking of PFC & vacuum vessel up to 300C
- 2011. 6 PF coil test up to 15 kA and startup, shaping

Contents

◆ Machine operation

- Vacuum in main vessel and cryostat
- Superconducting Magnet
- Machine control and DAQ system

◆ Plasma operation



- Start-up
- Plasma control

◆ Key system

- IVCC
- Heating



◆ H-mode in 2010

Vacuum Pressure during Campaign



- ◆ Baking on vessel wall(130 °C), pumping duct(120 °C) and PFC(300 °C)
- ◆ Routine(daily) GDC (Gaseous Discharge Cleaning) and boronization
- ◆ Base pressure was less than 8×10^{-8} mbar
- ◆ Water level drops after baking and boronization
- ◆ Pumping period for plasma experiment: 2 months at commissioning phase


Outgassing Rate of Vacuum Vessel



3rd Campaign




2nd Campaign



1st Campaign

Campaign	PFC area (unit : m ²)	Outgassing rate (unit : m·bar·ℓ·s ⁻¹)	Per unit area (unit : m·bar·ℓ·s ⁻¹ m ⁻²)	Baking system
1 st (2008)	1.54	1.43 × 10 ⁻⁴ (M 28 dominated)	9.31 × 10⁻⁵	• Vessel wall (100 °C)
2 nd (2009)	11	1.93 × 10 ⁻⁴ (M 02 dominated)	1.75 × 10⁻⁵	• Vessel wall and pumping duct (130 °C)
3 rd (2010)	54	6.49 × 10 ⁻⁴ (M 28 dominated)	1.20 × 10⁻⁵	• Vessel wall and pumping duct (130 °C) • Hot N2 gas on PFC (225 °C)
4 th (2011)	54	4.21 × 10⁻⁴ (M 28 dominated)	7.80 × 10⁻⁶	• Vessel wall and pumping duct 130 °C) • Hot N2 gas on PFC (300 °C)

Outgassing Rate of Cryostat





- ◆ He outgassing rate in the cryostat is the key parameter in the operation of SC magnet in terms of a good thermal barrier and Paschen discharge
- ◆ The outgassing rate increased year by year, however it was saturated around in the range of 10^{-5} mbar·ℓ/s.
- ◆ At 4th campaign, the vacuum pressure in the cryostat is 5×10^{-8} mbar.
(Note : Max. allowable pressure is 1.0×10^{-5} mbar)
- ◆ PF coil/structure circuit was suspected to be the dominant source of the cold leak.

	Total outgassing rate	Helium leak rate	unit
1st campaign	1.12E-07	8.92E-08	mbar·ℓ/s
2nd campaign	3.08E-06	2.45E-06	mbar·ℓ/s
3rd campaign	3.33E-05	1.47E-05	mbar·ℓ/s

TF Magnet Operation




- ◆ The TF magnet system was charged up to **35 kA**, which produced 3.5 T at the center of the vacuum vessel.
 - The coil temperature increase was below **0.2 K**
 - Maximum mechanical stress of the TF structure was 152 MPa, which is lower than the operational criteria of 500 MPa
 - Maximum radial displacement of toroidal ring is **less than 0.4 mm**.



PF Magnet Operation




◆ Normal plasma operation(#3267)

- Current ramp rate was usually less than 3 kA/s.
- PF 1&2 temperature rise was just up to **7.3K**.



◆ Abnormal operation (#3305)

- PF currents rise rapidly to recover I_p (20 kA/s)
- PF1 temperature rise was **10.79K**.



- ◆ Blip operation(100 ms) doesn't have large affect on the temperature rise.
- ◆ The temperature rise is influenced by Lhe coolant pass as well as di/dt (dB/dt) and duration time.

Machine Control with EPICS

◆ Machine Control System



- **Reliability and stability of CW superconducting machine**
- Integration of heterogeneous controllers:
 - VME, VXI, cPCI, PXI, PCI, PLC, and cFP
 - 32 control systems with 110 subsystems participated in 3rd campaign
- **Real time control based on the distributed network with EPICS**
 - No. of handling signals : ~ 50,000 I/O
 - Total operational data : 614 GB(daily increasing of data : about 5~6 GB)
 - Data storage : EPICS Channel Archiver

◆ DAQ System for Plasma Diagnostics

- **25 diagnostics systems synchronized with Local Timing Unit(LTU)**
 - No. of I/O : ~ 11,600 tags
 - Data stored to the MDSplus server/Central storage
 - Archived data at 2010 : 1794 GB/2,126 shots(daily increasing of data : about 40 GB)
- **a distributed clustered storage system for 2-D image advanced diagnostics**

Incoloy 908 in SC Magnet Coil Jacket

- Incoloy 908 in SC coil jacket as it has low thermal expansion coefficient compatible to Nb₃Sn.
- On the other hand, ferromagnetic incoloy 908 ($\mu \sim 10$) nonlinearly deforms magnetic field structure



Design value
of KSTAR:

$$R_0 = 1.8 \text{ m}$$

$$a = 0.5 \text{ m}$$

$$I_p = 2 \text{ MA}$$

$$k = 2.0$$

$$\delta = 0.8$$



$$B_0 = 3.5 \text{ T}$$

$$t_{\text{pulse}} = 300 \text{ s}$$

KSTAR superconducting coils		
Coil name	material	Amount
TF coil	Nb3Sn	16
PF1 Coil	Nb3Sn	2
PF2 Coil	Nb3Sn	2
PF3 Coil	Nb3Sn	2
PF4 Coil	Nb3Sn	2
PF5 Coil	Nb3Sn	2
PF6 Coil	NbTi	2
PF7 Coil	NbTi	2



Radial Bz Profile during Start-up



PF circuit with blip resistor


- The magnetic field structure near in-board side is affected by Incoloy
 - Without compensation, the deviation could increase up to 60 G
 - The deviation should be less than 20 G for successful startup
- Success shot rate increased up to **74.3 %** in 2010 (**21.5 %** in 2009)
 - Pure ohmic start-up was achieved with ~ 3 V of the loop voltage in 2010
 - Start-up w/o blip resistor was achieved for switching I_p direction.

Plasma Control System (PCS)

- ◆ **A fast, flexible control system in operation since 2008**
 - ◆ **Based on the Linux cluster tech, embedding 8 processes in a box**
 - Adapted from DIII-D PCS, with ~20 kHz control cycles
 - ◆ **Extended digital interfaces on reflective memory (RFM)**
 - ◆ **Integrated control capability for tokamak actuators**
 - Magnets, fueling, heating and IVCC etc.
 - Capable of getting ~200 plasma diag. through the built-in digitizers




Analog interfaces

Digital interfaces




Vertical Control and Shaping

- **Vertical stabilization is done with passive Cu plates and IVCC**
 - In-vessel vertical coil [IVC] installed behind the passive plates
 - PS spec. : ± 10 kA/turn, 960 V, PWM
 - **Design changes of the passive plates enhances control speed by 5 times**
 - Each up/down Cu plate is cut into 4 pieces
 - Gap resistance(2.1 mohm) per toroidal turn is attached







Magnetic shape control with real-time EFIT & isoflux algorithm







- **The real-time EFIT set as a shape verification tool for L-mode discharges as in 2010**
 - Based on the 12-element vessel model EFIT
- **Real-time shape control using iso-flux was verified in low-kappa a realm in 2010**
 - Extending to the well-balanced DND in 2011

In-vessel Control Coils



- 16 segmented modules
(4 circular coils for position Control and 12 FEC coils)
- $n=1$ and 2 capabilities, poloidally three coils (parity change)
- Wide physics experiment and flexibilities of control (IRC, FEC, RWM)

Diverter Operation




- **Double null operation**

- Two striking points are god agreement between EFIT & measurements by Langmuir probes (within ~ 2 cm)
- IR camera is available in 2011


- **In-vessel cryo-pump (IVCP)**

- Installation of IVCP was finished
- Tentative use LHe supply system for 1-2 years
- Open loop of LHe (from 1,000 liter dewar)
- **4 working hours per day/ lower diverter region**



H-mode in 2010




- Access to H-mode around $B_T \sim 2$ T
- $I_p = 600$ kA, $R \sim 1.8$ m, $a \sim 0.5$ m,
 $n_e > 1.4 \times 10^{19} \text{ m}^{-3}$, $\kappa \sim 1.8$
- Clear indication of L-H transition from D_α , W_{MHD} , XICS, ECE, CES, etc
- Low threshold power, $P_{\text{LH}} < 1.5$ MW
- Relative low density regime
- Marginal powers for L/H transition
 - Slow L/H transitions and dithering
 - Often synchronized with sawtooth crashes
- ELM filament dynamics revealed
- y 2-D ECEI measurement



Widely extended operation regime in KSTAR 2010



* Y.S. Park, S.A. Sabbagh, J.W. Berkery, et al. (accepted by Nucl. Fusion) (2011)



- In 2010, KSTAR operation regime was widely extended
 - β_N up to 1.3, Elongation up to 1.9
 - Triangularity up to 1.0
 - I_i covered: 0.8 to 1.9, but only circular has $I_i < 1.0$
- For $n=1$ RWM and vertical stabilities,
 - I_i should be decreased more

KSTAR joined the H-mode club in 2010

KSTAR Mission

- To achieve the **superconducting tokamak construction and operation** experiences, and
 - To develop **high performance steady-state operation physics and technologies** that are essential for ITER and fusion reactor development
-
- Based on achieving H-mode in 2010
 - In 2011 experimental campaign,
 - H-mode will be fully commissioned within given machine capability
 - ITER relevant/urgent, KSTAR specific research issues will be pursued
 - 1.5MW NB, 1MW ECH, and 1 MW ICRF are available in 2011
 - 15 MW auxiliary heating system will be available in 5 years.
 - So that we will prepare the second stage of KSTAR mission.

Summary

◆ Machine commissioning

- Vacuum of the vacuum vessel and the cryostat
- TF and PF coils are operated within the safety margin of SC magnet.
- Control systems based on distributed network and EPICS

◆ Plasma operation

- PCS for plasma shaping and Iso-flux control with real time EFIT
- Startup scenario compensating Incoloy
- H-mode in 2010

◆ Key system

- Picture framed in vessel coils(IVC, IRC, RMP, RWM, FEC)
- 1.5MW NB, 1MW ECH, and 1 MW ICRF is available
- 15 MW auxiliary heating system will be available in 5 years.

◆ ELM mitigation with RMP is the top priority in 2011

KSTAR Papers to SOFE 2011

SPL2-1 (invited) “Recent Experimental Results of KSTAR” M. Kwon

SO4C-2 (invited) “The Construction of ITER, Viewed from Lessons Learned from KSTAR Project” H. Y. Yang

- SP1-15 Design Feature & Operation Results of Kstar PFC GN2 Baking System S. T. Kim
- SP1-29 Investigation of the Radioactivity Inside the Kstar Vacuum Vessel after Shutdown by Using Gamma-Ray Spectrometry Y.S. Lee
- SP1-32 Temporal and Spatial PFC Temperature Profiles in KSTAR 2010 Campaign E. N. Bang
- SP2-24 Influence of Plasma Operation on the PF circulator of the KSTAR HRS System During 2010 Campaign H. J. Lee
- SP3-37 Conceptual Disign of the Kstar Motor Generator C. H. Kim
- SP3-39 Current Control Method of Thyristor Converter for PF superconducting Coil in KSTAR, H. S. Ahn
- SP3-40 Development of in-Vessel Vertical Coil Power Supply J. K. Jin