

Lessons learned in the construction of Wendelstein 7-X


Hans-Stephan Bosch
for the Wendelstein 7-X Team

Max-Planck-Institute for Plasma Physics, Greifswald, Germany



- Introduction
- Organisation of a big project - lessons learned
- Planning aspects - lessons learned
- Fabrication of components - lessons learned
- Integration - lessons learned
- Conclusions


W7-X, from theory to reality



major radius	5,5 m
minor radius	0,53 m
plasma volume	30 m ³
magnetic field	< 3 T
rot. transform	5/6 – 5/4
non-planar coils	50
planar coils	20

heating power	15 – 30 MW
pulse length	30 min
stored energy	600 MJ


device diameter	16 m
device height	4,5 m
device mass	725 t
cold mass	425 t




- Wendelstein 7-X is
- a first-of-a-kind device
 - numerically optimized, big scientific step
 - many new technologies to be developed
 - designed for high-power steady-state operation
 - 30 min plasma operation with 10 MW ECRH
 - superconducting magnet system
 - pressure water cooling of in-vessel components
 - a big machine
 - 30 m³ plasma volume, 750 t total weight
 - large and expensive components
 - demanding tools for fabrication and assembly
 - a cryogenic device
 - 425 t total cold mass
 - with high technical complexity
 - extreme quality demands in general

1991	EURATOM approval phase 1	1999	planned completion date
1995	EURATOM approval phase 2	2004	
1996	official project start	2006	
2000	inauguration of new building		
2002	insolvency Babcock GmbH (coil manufacturer) external audits of the project	2010	
2003	first restructuring of the project		
2004	device assembly interrupted due to coil repair second restructuring of the project	2012	
2005	assembly resumed		
2006	assembly plan revision counter measure package implemented	2016 2014	
2007	first magnet module completed		
2009	all magnets manufactured and tested assembly of four magnet modules in progress		
2011	all magnet modules assembled	2014	


All magnet modules completed




1st magnet module in lower shell of cryostat



Port assembly in first module, September 2010



4th module on machine base, April 2011



- Introduction
- **Organisation of a big project** - lessons learned
- Planning aspects - lessons learned
- Fabrication of components - lessons learned
- Integration - lessons learned
- Conclusions

Organisation

- clear responsibilities and structures are mandatory
- quick decision making must be secured
- structures are living and should be adapted to the phase of a project

But: often not compatible with the institutional reality

Strong project planning and coordination

- a professional full-time team is required
- this team must have a lead function in the project

But: planning basis is often weak, man power not available


Appropriate infrastructure/tools for the project

- QMS (ISO 9001) which defines/monitors the processes within the project
- (electronic) documentation of documents and CAD-models
- clear boundary conditions should be defined also for the technical level (handbooks, guidelines e.g. for materials, electronic or IT standards)


But: acceptance on the working level (scientists); “additional” effort

Evolution of project structure

1/2004




6/2011





Evolution of project structure

1/2004



6/2011





- Introduction
- Organisation of a big project - lessons learned
- **Planning aspects** - **lessons learned**
- Fabrication of components - lessons learned
- Integration - lessons learned
- Conclusions

Realistic planning of time, budget and staff

- typically the estimates are too low \Rightarrow continuous increases
- cost increases and delays damage the relation to funding agencies and to the public

But: estimates usually are fixed in an early stage: planning not yet detailed enough, little man power

Contingencies are necessary

- a reasonable contingency avoids permanent revision of the planning
- without contingency, decision-making (work processes) are slowed down


But: in many cases, a contingency is not granted


Appropriate planning and monitoring tools


- standard tools of PM must be available from the beginning (WBS (multi-level), milestone plans, trend analyses)
- detailed planning of work and finances (integrated planning)
- Earned Value Management \Rightarrow [A. Lorenz, SO4C-4](#)

But: acceptance on the working level has to be “enforced”

Cost evolution of W7-X







- Introduction
- Organisation of a big project - lessons learned
- Planning aspects - lessons learned
- **Fabrication of components** - **lessons learned**
- Integration - lessons learned
- Conclusions

Component design

- design has to be completed (and checked) before tendering
- design changes during the manufacturing have to be avoided
- clear specifications have to be provided

But: high time pressure and requirements on the fund flow

Fabrication skills and capacities

- industry should have proven the skills and know-how
- manufacturing capacities have to be secured
- complex consortia can be problematic - clear responsibilities preferred

But: monopoly situation and competition with other fabrication priorities

Technical risks during development and fabrication

- transfer of risk to industry is extremely expensive
- risks should be minimized by in-house development

But: high work-load in-house \Leftrightarrow large, competent team required

Prototypes, tests and quality assurance

- prototypes should be built when possible and affordable
- tests of prototypes and series products is mandatory
- QA also to be performed by the project
- close monitoring of the fabrication by project and by external inspectors


But: see above

Case: superconducting coils



- 50 non-planar coils, 5 types
- 20 planar coils, 2 types
- 243 NbTi strands
- Al cable-in-conduit
- 18.2 kA and 6 kV (non-planar)
- 16 kA and 4 kV (planar)
- 100M€ contract \Rightarrow consortium

W7-X coils – an European consortium



changes

- 1. cast steel casing instead of welded coil casing**
- 2. reinforcement of coil connection blocks***
- 3. reinforcement of planar coil casings***

* after revised structural calculations done at IPP

issues

- 1. deviations and damages of SC strands**
- 2. voids in cast steel coil casings**
- 3. geometrical deviations in coil casings**
- 4. residuals of Cu-SS soldering flux**
- 5. Al and SS welds to be requalified**
- 6. quench detection cable damage**
- 7. insulation faults in the coil header**
- 8. danger of shorts in the coil header**



insulation tests

- 13 kV in vacuum, RT and 4K
- also under Paschen-conditions
- current monitoring
- camera observation of coil header

complex & risky repair action

- 20 non-planar coils with systematic faults
- deep excavation of header area
- cracks and voids ← charged resin
- repeated Paschen tests
- repeated full cold test

- Introduction
- Organisation of a big project - lessons learned
- Planning aspects - lessons learned
- Fabrication of components - lessons learned
- **Integration** - **lessons learned**
- Conclusions

Management of surprises

- the project must be prepared for surprises
- risk identification and prevention required (mock-ups)
- in case of problems, clear procedures have to be available (CCB)

But: work load and (limited) experience of the staff; complex priorities

Tolerances

- maximum possible tolerance allowables should be foreseen
- fabrication and operation at the limits is costly and time-consuming

But: physics requirements are usually high


Margins

- margins and clearances should be as high as possible
- CAD tools and processes have to be installed (early) to handle geometry problems and space reservations ⇒ **C. Baylard, SO4C-5**


But: additional space is expensive; research facilities are complex and often at the technical limits

- 300 steel pipes and 24 superconducting bus-bars per module
- more than 500 welds and 24 superconducting joints per module
- three-dimensional stellarator geometry


Magnet module from inner side




Magnet module with bus-bars



Magnet module, bus-bars and cryo-piping





- 300 steel pipes and 24 superconducting bus-bars per module
- more than 500 welds and 24 superconducting joints per module
- three-dimensional stellarator geometry
- motion of magnets for different magnetic configurations up to +/- 15mm
- complex system of clamps and holders, stiff and flexible at the same time
- demanding design & manufacturing, intense metrology, complex change management
- extremely limited available space in the cryostat ← Design decision!

All projects have their individual history and development.

However, the main issues that have led to serious trouble in our project hold for any state-of-the-art fusion and non-fusion projects.

1. A competent project team must be available from the start. Where the know-how is not available, strong external institutional partners must be found and deeply integrated into the project.
2. A lack of reasonable margins, clearances and tolerance levels implies an uncontrolled increase of complexity and frequent changes. This has a strong impact on time, costs and man-power.
3. Major components must be thoroughly tested (prototypes) and qualified prior to tender action. The manufacturing process must be accompanied by an intense QA program. Quality management must be involved in each single step. Trained inspectors must follow up manufacturing in detail.

4. Clear project structures and responsibilities are mandatory. High-level management tools must be implemented and accepted on the working level. Formal procedures and written documents are unavoidable, but must be organized as pragmatic as possible.
5. Development and manufacturing risks should be taken to a large extent by the project. Industry cannot do that or will charge the project to cover unexpected costs, even beyond the contract. The only solution is to solve problems step-by-step with industry.
6. The construction of first-of-a-kind devices requires specialized in-house knowledge and specialized industrial suppliers. Often, a monopoly situation cannot be avoided and must be taken into account in design, planning and management.