


# The JT-60SA Project

P. Barabaschi, Y. Kamada, S. Ishida

for the JT-60SA Integrated Project Team




EU: F4E-CEA-ENEA-CNR/RFX-KIT-CRPP-CIEMAT-SCKCEN

JA: JAEA



Presented by E. Gaio  
on behalf of P. Barabaschi

# BA Agreement




Together with IFERC and IFMIF-EVEDA, JT-60SA is part of the « Broader Approach » agreement signed between Euratom and Japan

Entered into force in 2007

**66% of PAs signed so far.**


# JT-60SA Objectives

- A combined project of the **ITER Satellite Tokamak Program of JA-EU** (Broader Approach) and **National Centralized Tokamak Program in Japan**.
- **The mission:** contribute to the early realization of fusion energy by its exploitation to support the exploitation of ITER and research towards DEMO.





# The New Load Assembly

- JT60-U: Copper Coils (1600 T),  $I_p=4\text{MA}$ ,  $V_p=80\text{m}^3$
- JT60-SA: SC Coils (400 T),  $I_p=5.5\text{MA}$ ,  $V_p=135\text{m}^3$




# High Beta and Long Pulse

- JT-60SA is a fully superconducting tokamak capable of confining **break-even** equivalent class high-temperature deuterium plasmas ( $I_p^{\max}=5.5 \text{ MA}$ ) lasting for a duration (**typically 100s**) longer than the timescales characterizing the key plasma processes, such as **current diffusion** and particle recycling.
- JT-60SA should pursue **full non-inductive** steady-state operations with high  $\beta_N$  (**> no-wall** ideal MHD stability limits).




# Plasma Shaping


- JT-60SA will explore the plasma configuration optimization for ITER and DEMO with a wide range of the plasma shape including the **shape of ITER**, with the capability to produce both **single** and **double null** configurations.



**$I_p=5.5\text{MA}$ , Lower Single Null**



**$I_p=5.5\text{MA}$ , Double Null**



**$I_p=4.6\text{ MA ITER like}$**


# Phased Research Plan

- **Exploitation within the BA period will aim at the initial research phase:**
  - HH operation for plasma full commissioning
  - DD operation for identification of the issues in preparation for full DD operation
- Principles of “**Joint Exploitation**” later phases agreed between EU and JA
- Detailed “**Research Plan**” jointly prepared

	Phase	Expected Duration		Annual Neutron Limit	Remote Handling	Divertor	P-NB	N-NB	ECRF	Max Power	Power x Time
Initial Research Phase	phase I	1-2 y	<b>H</b>	-	R&D	LSN partial monoblock	10MW	10MW	1.5MW x100s + 1.5MW x5s	23MW	NB: 20MW x 100s 30MW x 60s duty = 1/30  ECRF: 100s
	phase II	2-3y	<b>D</b>	4E19			Perp. 13MW		33MW		
Integrated Research Phase	phase I	2-3y	<b>D</b>	4E20	Use	LSN full-monoblock	Tang. 7MW	7MW	37MW		
	phase II	>2y	<b>D</b>	1E21			41MW				
Extended Research Phase		>5y	<b>D</b>	1.5E21		DN	24MW		41MW	41MW x 100s	

## BA Agreement foresees


- Very limited size Project Team with mainly coordination functions
- Procurement Arrangements signed between Implementing Agencies
- -> “collaboration” between EU and JA.
- Considering this arrangement, a *Common Management and Quality Program* was developed to define R&R and common processes





# Sharing

- Japan and EU implement in-kind contributions for components.
- Existing JT-60U facilities will also be utilized.




# Machine Parameters

- After successful completion of the re-baselining in late 2008, the JT-60SA project was launched with the new design with the following parameters.

## Basic machine parameters

Plasma Current	5.5 MA
Toroidal Field, $B_t$	2.25 T
Major Radius, $R_p$	2.96
Minor Radius, $a$	1.18
Elongation, $\kappa_x$	1.95
Triangularity, $\delta_x$	0.53
Aspect Ratio, $A$	2.5
Shape Parameter, $S$	6.7
Safety Factor, $q_{95}$	$\sim 3$
Flattop Duration	100 s
Heating & CD Power	41 MW
N-NBI	10 MW
P-NBI	24 MW
ECRF	7 MW
Divertor wall load	15 MW/m <sup>2</sup>



## Variety of heating/current-drive/ momentum-input combinations

### NB: 34MWx100s

Positive-ion-source NB

85keV

12units x 2MW=24MW

COx2u, 4MW



CTRx2u, 4MW

Perpx8u, 16MW

Negative-ion-source NB

500keV, 10MW


Off-axis for NBCD




### ECRF: 110GHz, 7MW x 100s

9 Gyrotrons,

4 Launchers with movable mirror







- All SC Magnet
  - Nb<sub>3</sub>Sn for CS
  - NbTi for TF, EF
- 18 TF Coils
- 6 EF Coils
- 4 CS independent modules

# Conductors

Coil	TF	CS
Type of strands	$Nb_3Ti$	$Nb_3Sn$
Operating current (kA)	25.7	20
Nominal peak field (T)	5.65	~9
Operating temperature (K)	<5K	<5.1K
Number of SC strands/Cu strands	324 / 162	216 / 108
Local void fraction (%)	32	34
Cable dimensions (mm)	18.0 x 22.0	$\Phi 21.0$
Central hole (id x od) (mm)	-	7 x 9
Conductor ext. dimensions (mm)	22.0 x 26.0	27.9 x 27.9




TFC conductor



CS conductor



Conductor type	EF-H	EF-L
No. of coils	EF3, 4	EF1, 2, 5, 6
Type of strand	$Nb_3Ti$	←
Operating current (kA)	20.0	←
Nominal peak field (T)	6.2	4.8
Operating temperature (K)	5.0	4.8
Number of SC/Cu strands	450 / 0	216 / 108
Local void fraction (%)	34	34
Cable dimensions (mm)	21.8	19.1
Central hole (id x od) (mm)	7 x 9	←
Conductor ex. dimensions (mm)	27.7	25.0




EF-L&H conductor

# TF Magnet features



- Cable in Conduit Conductor , 72 turns, 25.7kA each
- 6 double pancakes, 6 turns/pancake. Helium inlets in high field side – joints in external low field side
- Windings enclosed in Steel Casings
- Steel casings supported to ground vertically and toroidally - connected in inboard curved regions by “Inner Intercoil Structure”
- Steel casings guided toroidally by “Outer Intercoil Structure” to support out of plane loads.



# View of Magnet - assembly




- **Conductor being fabricated**
  - **Strand: Furukawa**
  - **Cabling/Jacketing: ICAS**
- **Winding: contracts to be signed soon**
- **Casings: call for tender by summer**





# PF Coils – on site manufacturing

- Two buildings were constructed in Naka Site in 2009.




Two large PF coils (EF-1&6 coils) of 12m in diameter will be manufactured in this building because they are too big to be transported by using public road.


(2) **PF coil** manufacturing building constructed in March 2009



(1) **PF conductor** manufacturing building constructed in March 2009

The first superconducting conductor of 450m for the EF-4 coil has been completed in March 2010.






- Jacketing the superconducting cables and winding them around drums 3 m in diameter underway at the Superconducting Conductor Jacketing Building at the Naka Fusion Institute
- CS conductor also being fabricated
- First double pancakes of EF coils completed

# TFC Cold Tests

- All TFC will be cold (4.5K) tested at full current before shipping to Japan
- Test Facility will be in CEA-Saclay. Facility under preparation.
- PA prepared with test facility specifications and cold testing specifications
  - HV Tests, Leak Tests
  - Flow, Pressure Drop
  - Dimensional Stability during and after cooldown
  - Resistance, Joints
  - Tmargin, Quench tests (2 coils)
- Cryostat to be delivered in Saclay soon




# Power Supplies

A full new set of Power Supplies compatible with long pulse operation is being procured


## Toroidal Field circuit

- 18 SC coils grouped in 3 units of 6 coils
- One 6 pulse unidirectional thyristor converter, 25.7kA, 80V
- 3 Quench Protection Circuit (QPC) (1.5KV to ground)



## 10 Poloidal Field circuits FC, each coil with:

- 1 bidirectional 12 pulse converter 20kA, ~1KV (SCM\_PS)
- Switching Network Unit or Booster (old units)
- 1 QPC for fast discharge



## SCM-PS, SNU:

both PA signed, call for tender on-going


## QPC Units: Contract awarded Dec 2010

Detailed design phase just completed


oral presentation SO4D-2 on Thursday

# Vacuum Vessel

- Double Walled
- 18mm+18mm
- Boronised Water interspace (~160mm)
- 200C Baking




# Vacuum Vessel (2)



- **First Sector completed in Naka**
- **Tolerances well within requirement**

# MHD Control in-vessel components



## Error Field Correction Coil (EFCC)

- toroidal 6 x poloidal 2 coils (TBD)
- 30kAT (TBD)
- frequency  $\sim 100\text{Hz}$  (TBD)
- RMP for ELM control

## Fast Position Control Coil (FPCC)

- upper and lower coils
- 120kATurn
- time response  $< 10\text{ms}$
- VDE


## RWM control Coil (RWMC)

- toroidal 6 x poloidal 3 coils (TBD)
- 20kAT (TBD)

## Stabilizing Plate


- SUS316L
- Double Shell
- VDE & RWM

# Thermal Shields




Detailed design nearly completed  
Assembly studies underway  
Fabrication Trials underway


Double walled panel



VVTS





VVTS and PTS





VVTS, PCS and CTS



- Faceted
- Single wall
- Two parts (~650 Tonnes):
  - Main machine support
  - Cylindrical and lid
- Fabrication of Base started.
- Specifications for cylindrical body completed
- First component to be installed in torus hall. Delivery in Naka planned for Mid 2012



# Divertor Cassette



- CFC (type I and II) materials at the first stage were delivered at Naka in March 2009.



- Development of the divertor target is in progress to examine brazing for the divertor target.

- Fully water cooled PFC, in which CFC monoblock targets are partially installed.
- Carbon tiles are bolted on cooled heat sinks.
- RH compliant divertor cassette is adopted for future maintenance.



# Cryoplant

Strong effort in magnet design devoted to minimization of peaked loads by increasing as much as possible time constants.


Full TH model of TF magnet developed  
detailed industrial studies completed by 2 companies

Technical Specifications completed


Call for tender started




# JT-60 Disassembly underway




**High Voltage Deck of N-NBI**



**Neutron Shielding Wall**




Mar. 2010



**Torus Hall**

**Assembly Hall**



Sep. 2010

- JT-60SA has undergone a major rebaselining in 2008 in order to reduce costs while maintaining its objectives
- After successful completion of this re-baselining, the project has made a large progress in designing, manufacturing, planning and site preparation
- The procurement implementation for the components has progressed with relevant contracts following the PAs for the supply of **PF coils, vacuum vessel and divertor by Japan and power supply, cryostat, current leads and TF magnet by EU**. The majority of the PAs are either signed or in final preparation
- **Manufacturing activities** are now well underway
- Finally, as a consequence of the great Earthquake in Japan no major damage at JT60-U facilities as well as the involved factories were observed. Work is progressing well.

# Thanks for the attention!

